

## GAF-RE Training Workshop Yerevan, 11.05.2022

Promotion of Renewable Energies - GAF-RE Program Phase IV & V

# Disclaimer

---

The content of this document is intended for the exclusive use of Fichtner's client and other contractually agreed recipients. It may only be made available in whole or in part to third parties with the client's consent and on a non-reliance basis. Fichtner is not liable to third parties for the completeness and accuracy of the information provided therein.

# Revision status

---

Rev.	Date	Content/Amendments	Prepared	Checked
0	06.05.2022	Final draft	SM, MS, CM	Störring
1	10.05.2022	As presented	MS, CM	Störring

# Agenda

---

## **GAF-RE Training Workshop Part I**

---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-

# Agenda

---

## **GAF-RE Training Workshop Part II**

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

# Agenda

---

## **GAF-RE Training Workshop Part I**

- 1 Best practice design drawing package and design basis report
- 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
- 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
- 4 Module mounting compliant with support structure and warranty conditions
- 5 Support structure foundation methods, best practice and lessons learnt
- 6 Structural verification of support structure foundation -- field test vs. calculation
- 7 Personal Protective Equipment (PPE)
- 8 Required ESHS documentation at Site


# Best practice design drawing package and design basis report

---

## Best Practice EPC Guidelines


Fichtner has marked up the Guide

- **green highlighting** = best practices, recommendations
- **orange highlighting** = important PV plant feature that was (initially) missing at most projects



# Best practice design drawing package and design basis report

## Overview of engineering design stages, milestones and deliverables





# Best practice design drawing package and design basis report

---

## Design Basis Report – for what?

The point of Design Basis Report (DBR) is not a repetition of the data sheets and drawings that shall be provided separately anyway, but the **explanation** of the **design approach** and **assumptions** (such as design loads, site conditions, service life, etc.), as well as rationale for selection of specific structural components, mechanical and electrical systems, layout, etc.

A Design Basis Report can be structured as shown here →

- 1.0 GENERAL
- 1.1 INTRODUCTION
- 1.2 PROJECT SUMMARY
- 2.0 SYSTEM CONFIGURATION
  - 2.1 DC SYSTEM
  - 2.2 AC SYSTEM
  - 2.3 CIVIL
  - 2.4 MECHANICAL
- 3.0 ELECTRICAL EQUIPMENTS
  - 3.1 SOLAR PV MODULE
  - 3.2 DC CABLE
  - 3.3 INVERTER/PCU
  - 3.4 LV SWITCHGEAR
  - 3.5 LV CABLE
  - 3.6 CONVERTER TRANSFORMER
  - 3.7 MV CABLE
  - 3.8 MV SWITCHGEAR PANEL
  - 3.9 LV AUX.POWER SUPPLY
  - 3.10 SWITCH YARD EQUIPMENTS:
- 4.0 FACILITY FOR METERING SYSTEM AT INTERFACE POINT
- 5.0 OPERATIONAL PHILOSOPHY OF PCU IN GRID CONNECT SYSTEM
- 6.0 PLANT EARTHING SYSTEM
- 7.0 LIGHTNING PROTECTION SYSTEM
- 8.0 SITE SECURITY
- 9.0 PLANT MONITORING / SCADA SYSTEM

# Agenda

---

## GAF-RE Training Workshop Part I

---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-

# Installation challenges and lessons learnt

---

## Civil

Failure to design a site drainage can cause **erosion problems** to the following areas:

- foundations
- roads
- embankments

Due to the uncontrolled drainage, washed out concrete pile foundations can be observed at project site.



# Installation challenges and lessons learnt

## Civil



During Detailed Design, **water runoff vectors** (waterdrop paths) can be visualized by means of the Flow Paths tool in AutoCAD Civil 3D > [Analyze menu].

You can also define catchment areas through the tool "Catchments".

Runoff paths (white) perpendicular to contour lines (green/red), visualized by AutoCAD Civil 3D



Source:

<https://www.infratechcivil.com/pages/civil-3d-water-drop-path-tutorial-guide>




# Installation challenges and lessons learnt

## Mechanical

Issue	Impact	Example
<p>The mounting structure delivered to site is inconsistent with the design drawing. The delivered mounting structure purlin is a [ rail instead of a C rail</p>	<p>Provides <b>less mechanical strength</b> compared to the design structure.</p>	
<p>The PV modules are not bearing properly onto the purlins as indicated in the design drawing</p>	<p>Modules would <b>fall through</b> if not held by additional steel plates under the clamps, which is not a state-of-the-art mounting method.</p>	



# Installation challenges and lessons learnt

## Mechanical

Issue	Impact	Example
<p>Poorly installed or missing diagonal bracing:</p> <ul style="list-style-type: none"><li data-bbox="168 630 638 805">▪ Bracing profiles must be installed <b>at the rear side of the posts</b>, not in the module plane.</li><li data-bbox="168 853 638 1029">▪ Diagonal bracing must be <b>continuous</b> and not patched together.</li><li data-bbox="168 1077 638 1173">▪ Bracing profiles must be <b>rigid</b>, not buckling.</li></ul>	<p>The bracing installed cannot serve the purpose of improving the structure stiffness.</p> <ul style="list-style-type: none"><li data-bbox="667 630 1108 758">▪ Forces introduced will <b>distort</b> and <b>stress</b> the modules.</li></ul>	

# Installation challenges and lessons learnt

## Mechanical

Issue	Impact	Example
<p data-bbox="168 421 338 459">Corrosion</p> <ul data-bbox="168 512 613 1267" style="list-style-type: none"><li data-bbox="168 512 613 778">▪ PV structure posts should be <b>hot-dip galvanized</b> according to Industry Standard DIN EN ISO 1461 (75+ <math>\mu\text{m}</math> zinc coating)</li><li data-bbox="168 826 613 954">▪ If not galvanized, posts must have an excellent anti corrosive paint</li><li data-bbox="168 1002 613 1267">▪ For sheet metal that cannot be hot-dip galvanized, alternative coating systems like Magnelis® or PosMAC are available</li></ul>	<ul data-bbox="669 512 1133 778" style="list-style-type: none"><li data-bbox="669 512 1133 596">▪ Reduced material strength and lifespan</li><li data-bbox="669 644 1133 778">▪ Risk of structure failure and collapse/sagging of PV array</li></ul>	
		

# Installation challenges and lessons learnt

## Electrical

- Too **shallow cable laying** in trenches
- Trench depth not according to technical design (90 to 105 cm); actual cable depth observed at site 30-45 cm
- Cable trenches not cleared from **rock and debris**

## Impacts

- Risk of cable scratch and **Isolation failure**
- Cable heat dissipation not according to design > affects the current carrying capacity





# Installation challenges and lessons learnt

## Electrical



# Installation challenges and lessons learnt

---

## Electrical



- Connection not according to industry practice – ohmic losses, **overheating**
- Substandard cable installation work – **risk of short circuit**
- Junction box should be installed with suitable height above ground – **risk of water ingress**

# Installation challenges and lessons learnt

---

## Electrical



For indoor installation:

- All exposed busbars require a **shield** or perspex cover
- **Warning signage** to be applied on shield



For outdoor installation:

- **Barrier** should be provided to protect cables against accidental touch or being caught by under passing workers.

# Installation challenges and lessons learnt

## Electrical



### Issue

- DC string cable laying without **edge protection**
- Conduit end is open without proper **sealing**
- Fill factor!

### Impact

- Cable isolation scratch – **isolation fault**
- Water or pest ingress
- Current carrying capacity

# Agenda

---

## GAF-RE Training Workshop Part I

---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-

# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – PV Module

### Issue

#### PV module shading

- due to existing trees or infrastructure
- avoid as far as practicable
- potentially leads to module hotspots and early degradation



### Mitigation

- To be modelled into PVsyst if can't be relocated
  - as near shading scene for close objects to the PV array
  - as horizon/far shading for sufficiently far objects
- Possible mitigation by increasing the number of independent MPP trackers (sub-arrays connected to string inverters)





# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – Mounting structure

Issue	Mitigation	Example
<ul style="list-style-type: none"><li>Improper mounting structure pile foundation</li></ul>	<p>Soil investigation is essential - understand below ground underlying condition and dictates piling design</p>	
<ul style="list-style-type: none"><li>Use of unsuitable material as part of mounting structure connection members</li></ul>	<p>Proper study and calculation of structure - suitable design, material, dimension, securement methodology, load bearing capacity etc</p>	

# Installation challenges and lessons learnt



## Small-Scale and Rooftop PV – Mounting structure

Issue	Mitigation	Example
<ul style="list-style-type: none"><li>Use of improper method for piling securement</li></ul>	<p>Proper study and calculation of structure - suitable design, material, dimension, securement methodology, load bearing capacity etc</p>	
<ul style="list-style-type: none"><li>Mounting structure material and dimension selection appears inadequate</li></ul>	<p>Proper study and calculation of structure - suitable design, material, dimension, securement methodology, load bearing capacity etc</p>	



# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – Mounting structure

Issue	Mitigation	Example
<ul style="list-style-type: none"><li>▪ Use of non-designated module clamp - leads to damage module frame, deformation of clamp</li><li>▪ Module clamp securement not following OEM recommendation (bolt and nut with torque)</li></ul>	<ul style="list-style-type: none"><li>▪ Selection of clamps depending on PV module type - consult module supplier prior to procurement</li><li>▪ Always adhere to OEM installation manual</li></ul>	
<ul style="list-style-type: none"><li>▪ Module clamp bolt and nut can't be properly secured due to difficult location/hole at the structure - leads to scratches and corrosion build up</li></ul>	<p>Proper study and calculation of structure - suitable design, material, dimension, securement methodology, load bearing capacity etc</p>	

# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – Cabling

### Issue

- DC string cables
  - exposed to direct sunlight permanently (on the roof and on pole)- increase insulation degradation rate
  - not provided with suitable cable tray - no mechanical protection
  - laid in bundle - heat dissipation is questionable



### Mitigation

- Cable tray to be provided for DC strings at rooftop PV installation going to the inverter
- Amount of cable per tray to follow IEC standard, affects cable current carrying capacity



# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – Cabling


### Issue

DC string cables  
➤ installed with big loop - not according to IEC standard - leads to increased risk of potential lightning strike

Improper DC string cable fixation/securement/dressing at the back on module and at the mounting structure - difficulty to O&M team



### Mitigation

- String cables behind PV module to be installed such that to reduce "big loop".
- String cables to be secured using UV resistant cable ties at mounting structure. Attention should be given to sharp edges.




# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – AC and DC panel

Issue	Mitigation	Example
<ul style="list-style-type: none"><li>▪ Open holes and cable glands lead to ingress of small creatures, dust etc.</li><li>▪ Cables inside panel are not arranged properly.</li></ul>	<ul style="list-style-type: none"><li>✓ Spare cable glands to be sealed with suitable compound</li><li>✓ Panel cleaning as part of PM works by O&amp;M staff</li></ul>	
<ul style="list-style-type: none"><li>▪ Exposed busbar without Perspex cover/protection - Risk of electrocution.</li><li>▪ Holes are not properly sealed.</li></ul>	Panel to be manufactured according to relevant IEC.	

# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – AC and DC panel

Issue	Mitigation	Example
<ul style="list-style-type: none"><li>▪ Cables inside box are installed heavily on one side - leads to low heat dissipation, potential hotspot</li><li>▪ Cables are not provided with suitable labelling</li></ul>	<p>Labelling for cables inside panel (positive, negative, earthing, communication (if any), SPD etc.)</p>	

# Installation challenges and lessons learnt

## Small-Scale and Rooftop PV – Safety

Issue	Mitigation
<ul style="list-style-type: none"><li>▪ PV array installation too close to roadside. No proper barrier provided -<ul style="list-style-type: none"><li>➢ risk of property damage incident by vehicle, project delay, loss of generation.</li><li>➢ Increased soiling - loss of generation, reduce performance.</li></ul></li><li>▪ Inverter installation close to gas piping - increased risk of fire, difficulty for monitoring, trouble shooting and maintenance</li><li>▪ Earthing cable is not properly installed – risk of tripping hazard and theft</li></ul>	<ul style="list-style-type: none"><li>✓ Provide barricade or fencing around PV array installation area</li><li>✓ Road layout engineering design to consider risk of soiling to the PV module in addition to maintenance access</li><li>✓ Consideration of existing infrastructure for inverter location during design stage</li></ul>



# Agenda

---

## GAF-RE Training Workshop Part I


---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-

# Installation with clamps

## Improper module bearing

- The Solar First system clamps the module onto steel plates, not the **C profile** directly
- Steel plate (Q235B)
  - needs to introduce retaining force  $F_S$  into substructure
  - stressed for **bending**
- Structural calculation report shall include **proof** to this







# Installation with clamps

## According to module mounting manual




- The module frame is supposed to be retained between the **module clamp** and a **rigid mounting rail**
- **Overlap** module frame – mounting rail (shaded yellow below)



It is questionable that the module frame bearing on the steel plates is equivalent to the bearing on the mounting system rail as prescribed by the module manufacturer.

# Installation with clamps

**Module clamps** must be installed at the **location** (range) specified by **module manufacturer**


		Clamping System		
Installation		Maximum Load: Uplift load $\leq 2400$ Pa Downforce load $\leq 2400$ Pa	Maximum Load: Uplift load $\leq 2400$ Pa Downforce load $\leq 5400$ Pa	Maximum Load: Uplift load $\leq 2400$ Pa Downforce load $\leq 5400$ Pa
		Use four clamps $425\text{mm} < S < 625\text{mm}$ ■ Permissible Clamp Range	Use six clamps $290\text{mm} < S < 340\text{mm}$ $1020\text{mm} < L < 1070\text{mm}$ ■ Permissible Clamp Range	Use four clamps $475\text{mm} < S < 575\text{mm}$ ■ Permissible Clamp Range
				
		The guide rail should be installed parallel position to the long side of the frame	The guide rail should be installed parallel position to the long side of the frame	The guide rail should be installed perpendicular to the long side of the frame

- **Permissible** distance clamp to module edge:  $s = 425\text{...}625$  mm
- **Actual** edge distance is 347 mm  $\rightarrow$  outside of the range  $\rightarrow$  **module warranty void**
- support structure **design issue**
- **Check** this prior to construction, **reject** non-compliant support structure

## Installation with clamps

---

Lab test at TUV according to IEC 61215



- Test cycles with **2400 Pa** and **5600 Pa** (pressure)
- Module is tested / certified only with manufacturer-approved bearing / clamping

# Agenda

---

## **GAF-RE Training Workshop Part I**


---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-

# Support structure foundation methods, best practice and lessons learnt

## Current trend in Armenia

Install the module support structure on top of **concrete pile foundations** (popular method in China)



# Support structure foundation methods, best practice and lessons learnt

## Quality issues observed with concrete pile foundations

- **Poor quality** of concrete work resulting in **reduced strength**
  - **Voids** in concrete due to lack of vibrating
  - Positioning tolerance, **mismatch** with structure → insufficient anchor bolt **edge distance**
- Reinforcement cage issues
  - Rebar cage eccentric, **misaligned**
  - insufficient concrete cover
  - reinforcement **not reaching top** of concrete foundation (→ anchor bolts)
- Regular **testing** of concrete is required (cube compression test, slump test etc.)
- Managing the **interface** foundation – structure is always a challenge
  - Rammed post method avoids this!



# Support structure foundation methods, best practice and lessons learnt


## Quality issues observed with concrete pile foundations

- Expansion type anchor bolts may burst the concrete if **no reinforcement cage** is present. Reinforcement cage needs to sufficiently **overlap and surround** the anchor bolts.
- Remediation of **damaged concrete foundations** is possible but often ineffective.



*New rebar should tie in with existing rebar and be grouted into drilled holes. The mounting structure should be dismantled prior to remediation works.*

*New concrete should match full dimensions of existing foundation and sufficient cover to rebar achieved.*



*Example of good concrete foundation remediation works.*

# Support structure foundation methods, best practice and lessons learnt


---

## Quality issues observed with concrete pile foundations

When mounting structure and foundation are constructed by different parties:

- Need to **manage the interface\*** of two construction trades
- **QC and handover** of concrete foundation to structure installer (curing time for concrete needs to be considered)
- **Liability** issue, difficult recourse in case of damage due to high wind event or snow overload
- \*who is in charge of the anchor bolts?  
Sometimes the structure supplier delivers no or uncertified anchor bolts

→ selecting a different foundation method/ technology may be a better option





# Support structure foundation methods, best practice and lessons learnt

## Various mounting structure technologies used in the market - 1

Selecting the most suitable mounting structure depends on several variables: Ground conditions, project size, type of mounting structure, loads applied, availability of machinery, time schedule, costs, liability risks etc.

### Type

### Pro

### Con

#### Concrete Foundation



- No specialized machinery required
- **Common trade** that can be performed by local contractors
- Structurally very stable if constructed well
- Requires good **QC** and **interface** management
- **Liability** concerns
- Potential **access** issues for concrete trucks
- Less environmentally friendly (end of life **dismantling**)
- Potentially more expensive (especially for larger sites)

#### Rammed Steel Posts



- **Fast** and **cost-effective** method
- **Prefabricated** posts → less on-site QC
- **No trade interface**
- Requires **specialized machinery**
- Not suitable to **rocky ground** conditions
- Pile refusals require **pre-drilling + concrete**

# Support structure foundation methods, best practice and lessons learnt


## Various mounting structure technologies used in the market - 2

Type

Pro

Con

Steel Screw Pile



- Relatively **fast** and cost effective
- **Prefabricated** ground screws → less on-site QC
- Suitable to more ground condition types than rammed piles
- Easy recycling and **dismantling**

- Typically **trade interface**
- Requires **specialized machinery**
- Not suitable to **rocky ground** conditions
- More **expensive** than other options

Ballast



- Typically **prefabricated** → no on-site QC of concrete works required
- Anchoring design and **quality** better than on-site works
- Suitable for **most ground** types
- Fast installation
- Easy **dismantling**

- **Expensive** (especially if large ballast is required due to high wind forces)
- Possibility for movement of ballast which may cause stress on PV modules
- Not suitable for tracking systems

# Agenda

---

## GAF-RE Training Workshop Part I

---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-

# Support structure foundation -- field test vs. calculation

## Simple pull test

Easiest setup with

- backhoe excavator
- sling
- Crane scale
- Displacement measurement by yardstick inaccurate
- PPE!??



# Support structure foundation -- field test vs. calculation

## Simple pull test

Alternative option

- build mechanism out of wooden beams and
- apply the force using a hydraulic jack
- use crane scale to measure force



## Standard vertical jack

Double pump oil pressure, Lift faster, Lifting safe

There are 2 tons to 32 tons of car jacks,  
Complete tonnage range,  
Available for you to choose



# Support structure foundation -- field test vs. calculation

## Proof by calculation

According to ZTV-LSW 88, ZTV-LSW 06

- Calculation of pile foundation
- Standard originally for noise barrier walls


Program: Gründung  
 Project: Helios\_UC18\_20220504  
 Short : Helios\_UC18\_L1\_C1\_Ext

### Input data

Angle of slope beta	1.00	degrees
Angle of friction	32.00	degrees
Cohesion c	0.50	kN/m <sup>2</sup>
reduced to	0.25	kN/m <sup>2</sup>
Specific gravity gamma	18.00	kN/m <sup>3</sup>
Skin friction angle delta	16.00	degrees
Breadth of pole b	0.35	m
Safety eta	1.40	(-)
Affecting H-load H	3.75	kN
Affecting moment M	21.43	kNm
Initial depth	0.00	m

### Results of the calculations

H * Eta	5.25	kN
M * Eta	30.00	kNm
Depth of the centre of motion t	1.517	m
Sliding surface angle theta	20.31	degrees
Guiding line a	3.913	m
Gap length L	4.172	m
Surface F	2.97	m <sup>2</sup>
Soil resistance Eph1	77.54	kN
Soil resistance stress eph	292.16	kN/m <sup>2</sup>
Equilibrium force Eph2	72.29	kN
delta t for SumH=0 dt	0.35	m
<b>Necessary pole length l</b>	<b>1.87</b>	<b>m</b>
Maximal pole moment Mpf	22.41	kNm
Mpf * eta	31.38	kNm
ln a depth X0 =	0.39	m



### Layer 1

GRAVEL GROUND with sand filling  
 from 0.0 m – 2.0 m below ground surface.

Specific gravity $\gamma$ cal.	Angle of friction $\varphi$ cal.	Cohesion $c'$ cal	Skin friction (Breaking value)
kN/m <sup>3</sup>	°	kN/m <sup>2</sup>	MN/m <sup>2</sup>
18.0	32.0	0.5	0.030

# Support structure foundation -- field test vs. calculation

PRO and CON

## Advantages of pull tests

- A test is performed on site and demonstrates in this **experimental condition** that the profile can transmit the required forces.
- This implies quite a high level of safety.



## Disadvantages of pull tests

- The **soil structure** and overall soil **mechanical properties** are not explored. The soil below the driven profiles, which is also affected by the force application, remains unknown.
- The **effort** for the tensile tests is relatively **high** (pile-driving crew with truck, pile driver on tracked vehicle, wheel loader, geotechnical engineer with test equipment and measuring instruments).
- measurements are taken in a **situation** that will not occur later in practice, distorting the test results:
  - **pile-driving channel** considerably reduces the skin friction between profile and soil
  - profile surface is still very **smooth**, sometimes even oily from production

Fortunately, the described **weaknesses** of the **pull test** method are on the **safe side**. That means, the test results in a **lower** load capacity, compared to "settled" profiles in undisturbed soil after months → pull tests can be applied in many cases, even though they often result in unnecessarily large pile-driving depths (**oversizing**).

**Either pull tests or proof by calculation must be done! It is not included in the structure supplier's calculation!**

# Agenda

---

## **GAF-RE Training Workshop Part I**

---

- 1 Best practice design drawing package and design basis report
  - 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
  - 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
  - 4 Module mounting compliant with support structure and warranty conditions
  - 5 Support structure foundation methods, best practice and lessons learnt
  - 6 Structural verification of support structure foundation -- field test vs. calculation
  - 7 Personal Protective Equipment (PPE)
  - 8 Required ESHS documentation at Site
-



# Health and Safety

## First Aid kit

- The First Aid kit shall be provided at project site.
- The kit should at least contain necessary medicines with valid expiration date.



# Health and Safety

## Personal Protective Equipment (PPE)

### The minimum PPE set shall include:

- Safety helmet
- Gloves
- Hi-visibility vest
- Safety shoes (steel cap toe)

### During operation:

- Hi-visibility vest
- Dielectric gloves
- Dielectric shoes

### Other PPE depending on task:

- Harness – working at height
- Mask/Respirator – excavation, dusty conditions
- Etc




# Health and Safety

## Fire extinguisher

Fire extinguishers should be available near the transformer, hazardous waste storage, and flammable materials storage.

Portable extinguishers should also have valid expiry date.



# Health and Safety

Warning signage, tapes and posters

Warning signs and tapes shall be provided at the fences of the transformer, high voltage substation, electrical room as well as the plant area.

Signage must be bilingual.

Signage must be fixed, sturdy




- [ГОСТ 12.4.026-76 Система стандартов безопасности труда \(ССБТ\). Цвета сигнальные и знаки безопасности \(с Изменениями N 1, 2\) от 24 мая 1976 - docs.cntd.ru](#)

# Health and Safety

## COVID-19

- Responsible person, should be appointed by head of organization
- Awareness sheet according to Form N3 of the Order of the Minister of HealthCare should be placed at a visible location
- Facility to wash hands at the project site should be provided
- Monitor situation in accordance with Governmental Regulations



# Agenda

---

## GAF-RE Training Workshop Part I

---

- 1 Best practice design drawing package and design basis report
- 2 Installation challenges and lessons learnt (electrical, mechanical, civil)
- 3 Installation challenges and lessons learnt of small-scale and roof-top PV systems
- 4 Module mounting compliant with support structure and warranty conditions
- 5 Support structure foundation methods, best practice and lessons learnt
- 6 Structural verification of support structure foundation -- field test vs. calculation
- 7 Personal Protective Equipment (PPE)
- 8 Required ESHS documentation at Site

# Required ESHS documentation at Site

The following documents shall be available at the project site during the Construction and Operation Phase

## Construction

### **Permits and Licenses:**

- Power Generation License;
- Construction Permit;
- Land Ownership Certificates;
- Servitude Right Certificate for the OHL;
- Construction License for the Contractor Company (Including Energy Sector Certificate);
- The Letter of the Ministry of Environment Regarding no need for EIA expertise (for 110 kV insertion, one span) or the EIA expertise positive conclusion (if EIA expertise is required);
- ESHMP (including the Emergency Response Plan).

### **Logs:**

- Construction Log;
- Induction Register (available in any bookstore as well as on the internet GOST 12.0.004-2015)
- Accident Recording log (Form N2 of Decree of GoA N 458 dated 23.03.2006);
- COVID-19 Logs Form N 1 of the Decree of the Minister of Healthcare N17 dated 4.08.2020;
- COMPLAIN LOG/Grievance Register

## Operation

### **Permits and Licenses:**

- Power Generation License;
- Operation Permit;
- The Letter of the Ministry of Environment Regarding no need for EIA expertise (for 110 kV insertion, one span) or the EIA expertise positive conclusion (if EIA expertise is required);
- Land Ownership Certificate (updated to include the new structures);
- Servitude Right Certificate for the OHL;
- ESHMP (including the Emergency Response Plan).

### **Logs:**

- Induction Register (available in any bookstore as well as on the internet GOST 12.0.004-2015)
- Accident Recording log (Form N2 of Decree of GoA N 458 dated 23.03.2006);
- COVID-19 Logs Form N 1 of the Decree of the Minister of Healthcare N17 dated 4.08.2020;
- COMPLAIN LOG/Grievance Register

# ESHMP

---

## Environmental Social, Safety Health Management Plan

- Plan must be developed to ensure compliance during Construction and finally Operation.
- Standardization across all Projects and GAF
- Bi-annual report based on ESHMP (only 2)
- All incidents, accidents and errors = captured according to ESHMP and corrected accordingly
- Site visits by any authorized person can flag ESHMP non-compliance (non-compliance results in investigation)
- Investor ensure that they accept all aspects in ESHMP, as this document is vital for compliance
- ESHMP standards and requirements based on project requirements (KfW)



# Agenda

---

## **GAF-RE Training Workshop Part II**

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

# Agenda

---

## **GAF-RE Training Workshop Part II**

- |    |  |
|----|--|
| 9  | Efficient ways of pre-commissioning PV module string testing                         |
| 10 | Weather station for on-site irradiation measurement and plant performance monitoring |
| 11 | Bankable solar resource and energy yield assessments                                 |
| 12 | PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)              |
| 13 | Plant fencing and anti-intrusion best practice                                       |
| 14 | ESHS housekeeping  |
| 15 | Waste Management on and off site   |
| 16 | PV module disposal and recycling   |
| 17 | Environmental Offset, Botanical Studies  |

# Efficient ways of pre-commissioning PV module string testing

---

Test procedure – According to IEC standard

## **BS EN 62446-1:2016**

*Photovoltaic (PV) systems – Requirements for testing, documentation and maintenance. Part 1: Grid connected systems- Documentation, commissioning tests and inspection*



**IEC 62446-1**

Edition 1.0 2016-01

**INTERNATIONAL  
STANDARD**

**NORME  
INTERNATIONALE**



---

**Photovoltaic (PV) systems – Requirements for testing, documentation and maintenance –  
Part 1: Grid connected systems – Documentation, commissioning tests and inspection**

# Efficient ways of pre-commissioning PV module string testing

Test procedure – According to IEC standard

## Category 1 – PV string testing

The minimum requirement -

A standard set of tests that shall be applied to all systems.

Test regimes under Category 1 test regime include:

- **Continuity of protective earthing** and/or equipotential bonding conductors, where fitted
- **Polarity** test
- String **open circuit voltage** test
- String **short circuit current** test
- Functional tests
- **Isolation resistance**  $R_{ISO}$  of the DC circuits
- Combiner box test
  - A single string connected in reverse polarity within a PV string combiner box can sometimes be easy to miss. The consequence of a reversed string, particularly on larger systems with multiple often interconnected combiner boxes, can be significant. The purpose of the combiner box test is to ensure all strings interconnected at the combiner box are connected correctly.
- Tests of all AC circuits to the requirements of IEC 60364-6





Protocol String measurement							
customer:		inspected by:		approved by:			
plant:		signature:		signature:			
contractor:		date:		page:		total:	
weather conditions:		measurement device:		DOCUMENT No.			
responsible: Subcontractor		insulation proof voltage: 1000V		KTU-CH-String-2014-03-18-rev0			
electric circuit / string no.	solar cable A(mm <sup>2</sup> )	actual irradiation W/m <sup>2</sup>	voltage/current/isolation > 1MΩm				remarks
			Voc	Isc / A	I <sub>mp</sub> / A	Riso / MΩm	

# Efficient ways of pre-commissioning PV module string testing

Test procedure – According to IEC standard

To be efficient, multipurpose and multifunctional test equipment is recommended



Equipment which can conduct multiple tests concurrently

Brand	Model	Test capability	
Seaward <a href="http://seaward.com">795 (seaward.com)</a>	Solar utility pro test kit	Open circuit voltage ( $V_{oc}$ ) Short circuit current ( $I_{sc}$ ) Polarity check Isolation resistance	
Solmetric PV Analyser <a href="http://solmetric.com">PVA-1500V4 PV Analyzer Kit (solmetric.com)</a> <a href="http://yimg.com">PVA1500 ProductSheet sm2.pdf (yimg.com)</a> <a href="http://yimg.com">PVA User's Guide (yimg.com)</a>	PV Analyser	I-V curve tracer, P-V curve tracer $V_{oc}$ $I_{sc}$ measurements	
HT Italia <a href="http://ht-instruments.com">PV-ISOTEST   Commissioning and Maintenance   HT Instruments (ht-instruments.com)</a>	PV ISOTEST	Isolation resistance measurement Continuity of protective conductor	
HT Italia <a href="http://ht-instruments.com">1500V I-V Curve Tracer I-V500w   HT Instruments (ht-instruments.com)</a>	SOLAR I-V500w	I-V curve tracer $V_{oc}$ $I_{sc}$	

# Efficient ways of pre-commissioning PV module string testing

Test procedure – According to IEC standard

To be efficient in string level testing, multipurpose and multifunctional test equipment is recommended



Quick testing string by string at combiner box or string inverter input

Sample of test result output using Seaward handheld equipment



Source:

[795 \(seaward.com\)](https://www.seaward.com)

# Efficient ways of pre-commissioning PV module string testing

Test procedure – According to IEC standard

To be efficient in string level testing, multipurpose and multifunctional test equipment is recommended



Example using HT Italia for Isolation resistance test of PV string using different modes

A worker using Solmetric PV Analyser for PV string testing

Sources:





- <https://www.ht-instruments.com/en/products/pv-isotest/download/brochure/>
- [PVA-1500V4 PV Analyzer Kit \(solmetric.com\)](https://www.solmetric.com/PVA-1500V4-PV-Analyzer-Kit)

# Efficient ways of pre-commissioning PV module string testing

Test procedure – According to IEC standard

## Category 2 – I-V curve tracing

An expanded sequence of tests for in-depth system performance analysis and trouble shooting



Source:

<https://www.ht-instruments.com/en/products/solar-i-ve/download/brochure/>




# Efficient ways of pre-commissioning PV module string testing

Test procedure – According to IEC standard

## String I-V curve test (I-V curve tracing)

More measurement parameters besides  $V_{oc}$ ,  $I_{sc}$ :  
e.g.  $V_{mpp}$ ,  $I_{mpp}$  and  $P_{max}$  etc.

The shape of I-V curve (and the parameters) can be interpreted to identify potential issues/problems (and its causes) of the system including:



1. **Steps or notches** in curve are indications of **mismatch** between different areas of the array or module under test.
2. **Low current** – A number of factors can be responsible for a variation between the expected current and the measured current (array causes, modelling cases, or measurement causes)
3. **Low voltage** – Potential causes for a variation in voltage (Array causes, modelling causes, or measurement causes)
4. **Rounded knee** - Rounding of the knee of the I-V curve can be a manifestation of the **aging process**. Before concluding that this is the case, check the slopes of the horizontal and vertical legs of the I-V curve. If they have changed, it can produce a visually similar effect in the shape of the knee.
5. **Shallower slope** in vertical leg – The slope of this portion of the I-V curve between the maximum power point ( $V_{mpp}$ ) and  $V_{oc}$  is influenced by the **series resistance** to the circuit under test. An increased resistance will reduce the steepness of the slope, due to PV wiring damage or faults (or cables insufficiently sized), faulty or poor connections, increased module series resistance.
6. **Steeper slope** in horizontal leg - A variation in slope in the upper portion of the I-V curve is likely due to: Shunt paths in PV cells, Module  $I_{sc}$  mismatch, tapered shade or soiling (e.g. dirt dams)

I-V curve interpretation and troubleshooting poster: [SolarPro I-V feature article, Hernday.pdf \(solmetric.com\)](#)

# Efficient ways of pre-commissioning PV module string testing

## String monitoring facility of PV array

### Overview

- Additional equipment provided inside the combiner box or string inverter
- Measurement of **individual string current** in real time
- Combined application with Plant monitoring system (SCADA)
- String-level status available in SCADA

### Importance

- Ability to monitor individual strings
- Improve troubleshooting time and enable **quick identification of defects** by the Operation and Maintenance (O&M) team
- Prevent accumulative malfunction of modules or strings
- Reduce downtime

### Example




# Efficient ways of pre-commissioning PV module string testing



## PV array infrared imaging – drone survey

### ■ PV array infrared camera inspection

The purpose of an infrared (IR) camera inspection is to detect **unusual temperature variations** in operating PV modules in the field. Such temperature variations may indicate problems within the modules and/or string, such as reverse-bias cells, bypass diode failure, solder bond failure, poor connections and other conditions that lead to localized high temperature operation (**hotspots**).



Source: NREL




This so-called 'string-end heating pattern' (SEHP) is highly suggestive of PID

# Efficient ways of pre-commissioning PV module string testing

IR drone survey – indicative pricing


## IR drone survey cost/MWp



- The cost of IR drone survey decreases exponentially with MWp
- Duration to complete depending on location, plant capacity and availability of surveying team
- Reporting can be done with web-based portal for interactive information sharing

# Efficient ways of pre-commissioning PV module string testing

## Commissioning Milestones



SOURCE: World Bank Group.

# Agenda

---

## GAF-RE Training Workshop Part II

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

# Requirements for solar irradiation measurement

---

## Measurements of solar irradiation

- **On-site measurement** relevant for:
  - Verification during plant acceptance and operation phase (performance control / review of guarantees)
  - Optimization / validation of solar maps & satellite data
- Long-term measurement is **not** necessary for project development (compared to CSP or Wind energy)
- For bifacial modules, ground **albedo** can be measured locally for certain period of time



Pyranometer (Kipp & Zonen)



Albedometer (2 pyranometers)

# Requirements for solar irradiation measurement

- **Pyranometers:** high measurement accuracy, measure the complete solar spectrum, good self-cleaning effect, reflects satellite irradiation data, expensive (about 2,000 €), usually required in project finance
- **Reference cells:** medium-low accuracy, measure the spectrum of the solar cell, prone to soiling, economic (starting at around 100 €)



Pyranometer & reference cells



Reference cell



Shadow ring



# Solar Irradiation for PV Application

---

**Pyranometers:** high measurement accuracy, measure the complete solar spectrum, good self-cleaning effect, reflects satellite irradiation data, expensive (about 2,000 €), usually needed in project finance.

**Reference cells:** medium-low accuracy, measure the spectrum of the solar cell, prone to soiling, economic (starting with around 100 €).

**Shadow ring:** to measure diffuse irradiation.



Pyranometer



Reference cell




Shadow ring

# Weather station for on-site irradiation measurement

## Minimum Technical Requirements

### Renke model RS-QXZN-M

- **Horizontal irradiation** (GHI)
- **Tilted irradiation**
- Ambient temperature
- Module temperature (to be installed at module)
- Wind speed and direction



### **Plant Performance Monitoring**

Data from the **weather station**, **inverters**, **combiner boxes**, **meters** and **transformers** to be collected in data loggers and passed to a plant monitoring system. Monitoring system to include the **inverter / string monitoring** data, **production** data from the export meter, the data from the **meteo station** and module temperature sensor, to raise warnings on a daily basis in case of errors, defects or a performance shortfall

# Agenda

---


## GAF-RE Training Workshop Part II

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

# Bankable solar resource and energy yield assessments (EYA)

## EYA approach summary



# Requirements for solar irradiation data

---

## Types of **solar resource data** — PROs and CONs

- **Data from national meteorological stations / institutes**
  - **interpolation** of data for project location, long-term data
  - programs available with **worldwide data base** like Meteonorm or PVGIS\*
    - depending on the region high **uncertainties**
    - sometimes **correlation** with satellite data
  - simulations possible
- **satellite data**
  - **exact project location** (coordinates), **10 years and more** available
  - **different sources** with different quality
  - suitable for simulation (yield study), bankability is given
  - industry leader: Solargis
- **on-site ground measurement**
  - **High accuracy** with high quality equipment possible **if well maintained**
  - **Cost and time** effort (min 1 year of data required)
  - Usually for performance control during operation (PR)

Long-term, high-quality **satellite data is “bankable”**. They are the basis to evaluate and develop utility scale PV projects. Costs for a data set is about 1,000 € or even less.

\* <https://ec.europa.eu/jrc/en/pvgis>, <https://meteonorm.com/>

# Solar Irradiation for PV Application

---




- Irradiation (**GHI**, DIF, DNI)
- Global irradiation on tilted surfaces (GTI or POA plane of array irradiation)
- ambient temperature (TEMP)
  
- Historical time-series
- Recent time-series - data for a continuous 12-month period
  - remember, PR is a **long-term KPI** across multiple seasons
- Typical Meteorological Year (**TMY**) = historical time series synthesized into one year
- Forecast data - Forecast horizon of up to 72 hours
- PVSyst input files

**Long-term** high-quality satellite data is “bankable”. It is the basis to evaluate and develop utility-scale PV projects. Costs for a data set are about 1,000 € or even less.

Pyranometers are used to measure the irradiation during the plant operation.

# Bankable solar resource and energy yield assessments

## Example of solar irradiation map



# Bankable solar resource and energy yield assessments

## Energy Yield Assessment (EYA)

- Software to be utilized (industry standard)



- System design set up in PVsyst and loss diagram (Sankey diagram)

Grid system definition, Variant VCD: "First simulation: simple system without perturbations"

**Sub-array**

Sub-array name and Orientation: Name: PV Array, Tilt: 25°, Azimuth: 20°

Presizing Help: Enter planned power: 16.1 kWp, or available area(modules): 125 m²

Select the PV module: Generic, 190 Wp 22V, Si-poly, Poly 190 Wp 54 cells, Since 2015, Typical, Maximum nb. of modules: 85


Select the inverter: Generic, 4.2 kW, 125 - 500 V, TL, 50/60Hz, 4.2 kWac inverter, Since 2012

Design the array: Mod. in series: 13, Nb. strings: 6, Overload loss: 0.0%, Phom ratio: 1.18, nb. modules: 78, Area: 115 m²

Operating conditions: Wmpp (60°C): 286 V, Wmpp (20°C): 346 V, Woc (-10°C): 478 V, Plane irradiance: 1000 W/m², Imp (STC): 43.8 A, Isc (STC): 46.9 A, Isc (at STC): 46.9 A

Global system summary:

Parameter	Value
Nb. of modules	78
Module area	115 m²
Nb. of inverters	3
Nominal PV Power	14.8 kWp
Maximum PV Power	13.8 kWDC
Nominal AC Power	12.6 kWAC



Source: [Features – PVsyst](#)



# Bankable solar resource and energy yield assessments

## Energy Yield Assessment (EYA) – Simulation approach

- Plant design
  - According to the information, document, data, drawing provided by **Designer** / EPC contractor
  - **.PAN** and **.OND files** for PV module and inverter respectively is important
  - Typical plant design and characteristics

PV_PLANT_NAME	Data
Installed capacity (DC peak power)	
Total power (AC) nom. inverter output	
Number of strings	
<b>PV modules</b>	
Manufacturer	
Module type	
Nominal power at STC	
Technology	
Bifaciality Factor	
Number of modules	
Number of modules per string	
<b>Mounting system</b>	
Manufacturer	
Inclination of modules / Orientation	
Installation type	
Limit shading angle	
Pitch distance	
Height above ground	
<b>Inverters</b>	
Inverter manufacturer	
Inverter type	
Rated input power	
Number of inverters	
Number of strings per inverter	
<b>Cabling</b>	
Max./Calculated DC ohmic losses	
Max./Calculated AC losses	
<b>MV transformers</b>	
Transformer type	
Number of transformers	
Iron and resistive losses	
<b>HV transformers</b>	
Transformer type	
Number of transformers	
Iron and resistive losses	
<b>Soiling</b>	
Soiling losses including cleaning	

# Bankable solar resource and energy yield assessments

PR is simply the specific energy yield divided by the specific irradiation

## ➤ PVsyst simulation process

### ▪ Performance Ratio (PR)

- considered as the ratio (annual values) of total AC energy to the theoretically available energy
- can be considered as the relationship between the effective and the theoretical (module operation at STC conditions) electricity production of a photovoltaic system measured at the relevant energy meter.
- represents module performance that deviates from the standard conditions together with additional losses between module and relevant energy meter.
- related to the peak capacity and can be determined for any period (usually annually).

• The PR is defined as 
$$PR = \frac{Y_{AC}}{G_{TILT} \times A_{1kW} \times \eta_{STC}}$$

where

$Y_{AC}$	=	specific AC electricity yield
$G_{TILT}$	=	total global solar irradiation sum on the tilted module plane
$A_{1kW}$	=	area of a 1 kWp PV module array and
$\eta_{STC}$	=	PV module efficiency at standard test conditions.

$$PR \text{ easy} = \frac{\text{specific yield}}{\text{specific irradiation}}$$

$$PR = \frac{\text{Yield}}{\text{Irradiation}} \frac{\frac{kWh}{kWp}}{\frac{kWh}{m^2}} \times 1000 \frac{W}{m^2}$$

# Bankable solar resource and energy yield assessments

## Energy Yield Assessment (EYA) – Simulation approach


### ➤ Losses

Modeled in PVsyst	Additional losses
Mismatch	Initial degradation
Module quality factor	Annual degradation
DC losses	Own consumption
AC losses	Plant availability
Transformer losses	Grid availability
Soiling losses	

Reactive power generation

### ➤ Typical PVsyst simulation results table

Site	Annual pwr generation (MWh)	Installed DC PV power (kWp)	Specific yield (kWh/kWp)	GHI (kWh/m <sup>2</sup> )	POA irradiation (kWh/m <sup>2</sup> )	Performance ratio (%)
Sharosolar-1	9476	5856	1618	1764	2021	80.05




# Bankable solar resource and energy yield assessments

## Energy Yield Assessment (EYA) – Simulation approach

### ➤ Probability Analysis

- The **probability** of electricity production exceeding a certain percentage of the calculated output is determined by the total **uncertainty**
- Example of output table showing **uncertainty** and the **probabilities of energy generation** including additional losses and initial degradation:

Duration (years)	1	2	3	4	5	10	20
Total uncertainty (%)	7.4%	7.3%	7.3%	7.3%	7.2%	7.2%	7.2%
P50	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%
P75	95.0%	95.1%	95.1%	95.1%	95.1%	95.1%	95.1%
P90	90.6%	90.7%	90.7%	90.7%	90.7%	90.7%	90.7%
P95	87.9%	88.0%	88.1%	88.1%	88.1%	88.1%	88.1%
P99	82.9%	83.0%	83.1%	83.1%	83.2%	83.2%	83.2%
P50 (kWh/kWp)	1,993	1,993	1,993	1,993	1,993	1,993	1,993
P75 (kWh/kWp)	1,894	1,895	1,896	1,896	1,896	1,896	1,896
P90 (kWh/kWp)	1,805	1,807	1,808	1,808	1,808	1,808	1,809
P95 (kWh/kWp)	1,752	1,754	1,755	1,756	1,756	1,756	1,757
P99 (kWh/kWp)	1,652	1,655	1,657	1,657	1,658	1,658	1,659



# Bankable solar resource and energy yield assessments

## Energy Yield Assessment (EYA) – Simulation approach

### ➤ Final output

- Example of specific yield figures including additional losses and total degradation over 20 years

Year	P50	P75	P90	P95	P99	Total degradation	Annual PR incl. degr.
1	1,993	1,896	1,809	1,757	1,659	0.75%	80.2%
2	1,983	1,887	1,800	1,748	1,650	1.25%	79.8%
3	1,973	1,877	1,791	1,739	1,642	1.75%	79.4%
4	1,964	1,868	1,782	1,730	1,634	2.25%	79.0%
5	1,954	1,859	1,773	1,722	1,626	2.75%	78.6%
6	1,944	1,849	1,764	1,713	1,618	3.25%	78.2%
7	1,934	1,840	1,755	1,705	1,610	3.75%	77.8%
8	1,925	1,831	1,747	1,696	1,602	4.25%	77.4%
9	1,915	1,822	1,738	1,688	1,594	4.75%	77.0%
10	1,905	1,813	1,729	1,679	1,586	5.25%	76.7%
11	1,896	1,804	1,721	1,671	1,578	5.75%	76.3%
12	1,886	1,795	1,712	1,662	1,570	6.25%	75.9%
13	1,877	1,786	1,703	1,654	1,562	6.75%	75.5%
14	1,868	1,777	1,695	1,646	1,554	7.25%	75.1%
15	1,858	1,768	1,686	1,638	1,546	7.75%	74.8%
16	1,849	1,759	1,678	1,629	1,539	8.25%	74.4%
17	1,840	1,750	1,670	1,621	1,531	8.75%	74.0%
18	1,831	1,741	1,661	1,613	1,523	9.25%	73.6%
19	1,821	1,733	1,653	1,605	1,516	9.75%	73.3%
20	1,812	1,724	1,645	1,597	1,508	10.25%	72.9%

# Agenda

---

## GAF-RE Training Workshop Part II


---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

---

## O&M Contract Salient Point



# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

---

## O&M Contract Salient Point – Scope of Work

### Preventive maintenance (PM)

**Activity** and **frequency** of preventive maintenance is set by the operations function and is influenced by a number of factors, such as equipment type, environmental conditions at the site (e.g., marine, snow, pollen, humidity, dust, wildlife), and **warranty terms**.

- Scheduled maintenance is often carried out at intervals to conform to the **manufacturers' recommendations**, as required by the equipment warranties. Check available **long-term service agreements** (LTSA) for inverters.
- Any **scheduled recurring** activity such as remote data acquisition and processing, e.g., to calculate performance KPIs is part of preventive maintenance
- **PV module cleaning** normally is considered part of preventive maintenance, and it is critical as it relates to the assumption in the yield study and **directly impacts the energy output** of the Project. Module cleaning can be due to soiling/dust or snow.

### Corrective maintenance (CM)

Required to **repair** damage, malfunction or **replace** failed components. Critical **spare parts** to be kept on stock for a fast response.

- It is possible to perform some corrective maintenance such as inverter resets or communications resets remotely.
- Less urgent corrective maintenance tasks can be combined with scheduled, preventive maintenance tasks.

Source: NREL best practices for OnM PV ESS 73822.pdf



# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

## O&M Contract Salient Point – Scope of Works

### Preventive Maintenance

- **PV module**
  - Visual inspection
  - Thermography
  - I-V curve
- **Combiner box**
  - Visual inspection, incl. SPD
  - Cleaning
  - Thermography
- **Mounting structure**
  - Visual inspection
  - Torque check
  - Corrosion protection thickness
- **Inverter**
  - According to OEM's recommendations including filter and ventilation maintenance
- **Meteorological equipment**
  - Cleaning
  - Calibration
- **MV equipment, power evacuation facility**
  - According to OEM's recommendations
- **Civil works**
  - Drainage
  - Fencing
  - Road
  - Vegetation
  - Building (if applicable)

S323Doc-1378869599- 10491

### Corrective Maintenance

- **PV module**
  - Cracks
  - Hot spots
  - Loose connector
- **Combiner box**
  - Blown fuse/fuse holder
  - Loose connection
- **Inverter**
  - Alarms and faults
- **MV equipment**
  - Alarm and faults
- **Meteorological equipment**
  - Invalid data
- **Spare part management**
  - replenish spare part stock after component replacements
  - keep the digital inventory up to date



Source: NREL best practices for OnM PV ESS 73822.pdf

### PV Module Cleaning

- **Dust and soiling**
  - Manual cleaning by manpower
  - Robot assisted cleaning
- **Snow cleaning**
  - By powerful turbo-fan, not shovel or other mechanical means



Source: NREL best practices for OnM PV ESS 73822.pdf



Source: 210303 OM Manual EN.pdf

# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

## O&M Contract Salient Point – **Availability Guarantee**

### Definition

- The percentage of **uptime** that a component or system is operating.
- Important to distinguish events that are **outside management control** such as grid availability, grid curtailment. Operators should not be penalized for such events.
- The energy availability may be reported for the complete system or for **building blocks** within systems.
- Availability can also be specific to the components or subsystems within a system e.g., tracking system, inverter.

### Availability

### Guaranteed Availability

Typically, 98 or 99% - derived from uptime of the system

$$\text{PV System Availability} = 1 - \frac{1}{H_{tp} \times KW_{np}} \times \left( \sum_{\text{Incident}} (H_{un} \times KW_{dr}) \right)$$

Where:

Theoretical total production time (H<sub>tp</sub>):

The hours in the period when sufficient sunlight exists to allow the inverters to reach the input voltage needed to operate.

Nameplate power (KW<sub>np</sub>):

The nameplate power rating of the entire solar generating facility determined by the sum of each module's nameplate kWp rating.

Component unavailability hours (H<sub>un</sub>):

The hours in the period when solar irradiance is sufficient to power the inverters, yet a component within the facility is not available to generate power due to an equipment fault.

Derated system power (KW<sub>dr</sub>):

The value for unavailability derated system power will be calculated by the amount of unavailable DC nameplate capacity for the period and is determined by sum of each module's

Incident:

Every outage incident during the measurement period.

Note 1: KW<sub>dr</sub> describes the fractional capacity reduction (not due to degradation).

Note 2: This calculation does not consider cumulative degradation, which should be calculated and tracked separately along with energy production.

# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

## O&M Contract Salient Point – Other forms of Guarantee

### 1 Energy availability

energy availability is a metric of energy throughput capability that quantifies the expected energy when the system is operating relative to the total expected energy

### 2 Energy performance index

comparison of the energy that was produced by the plant with the energy that was **expected** for the plant based on the measured weather and **irradiance**, and a **performance model** agreed to by the stakeholders.

### 3 Energy delivery

measured MWh/year energy delivery

$$PR = \frac{\frac{\text{kWh}}{\text{kWp}}}{\frac{\text{kWh}}{\text{m}^2}} \iff \frac{\text{kWh}}{\text{kWp}} = \frac{\text{kWh}}{\text{m}^2} \times PR_{[EYA]}$$

### 4 Specific performance

energy delivery divided by plant rated capacity, in units of kWh/kW/year

### 5 Performance Ratio (PR)

a measure of **PV plant capability**, of how effectively the plant converts sunlight collected by the PV panels into AC energy delivered to the off-taker; plant Design must include a final EYA → **PR<sub>EYA</sub>** is the basis for minimum guaranteed performance

### 6 Power performance index

similar to the energy performance index except that it reflects the power output rather than the energy output

# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

## O&M Contract Salient Point – Spare parts

- Based on EPC and **manufacturer recommendations**, e.g., inverter "first aid kit"
- **Inventory management** – replacements of spare parts need to be ordered based on component failure history, balance on stock, lead time, reordering amount, storage requirements etc.
- Good practice for **inventory management**:
  - Strategically locate a **warehouse** to share stock and reduce travel time; **sharing spares** for long-lead-time items such as inverters and transformers across multiple projects in a portfolio
  - **Standardizing** certain supplier and models to reduce diversity in stock
  - Making arrangements with **suppliers** to guarantee availability or consignment stock with the manufacturer.
  - Storage of spare parts to be provided accordingly – indoor for electronics and sensitive equipment, outdoor under shed for outdoor equipment.



Spare Part List SC-XXX-CP

Category	Item designation	SMA order number	Description	Build-in quantity	Retail price / piece
Circuit Breaker	SC-Q5	60-9045	switch-disconnector 1SDA 4-pole-with accessories ABB	1	3.816,87 €
		60-90455	undervoltage tripping device ABB 1SDA062087R1	1	105,60 €
Fuses	SC-F20, -F21, -F22, -F23, -F24	61-117306	Circuit breaker 3pol 6A S203-B6 ABB	1	51,00 €
		10-6404	Strikesorb 40-F Raycap	3	288,00 €
		10-6405	Strikesorb 40-F Raycap	2	288,00 €
		62-951315	kombi-arrestor, modular (type 1) 3+1pol.-400VAC	1	996,21 €
Relays, power contactors	SC-F29	62-951001	protection modul Dehrentent, Dehn 951001	3	302,40 €
		62-951100	protection modul Dehrentent, Dehn 951100	1	375,30 €
		61-1263161	circuit breaker 3+NA pol K16A ABB S203-K16	1	58,50 €
		60-000390	contactor ABB AF 1650T-30 w. FRT-option	1	4.816,80 €
		60-00100091202	power contactor 400VAC 9A 3pol 24VDC	1	30,72 €
Switch cabinet heating	SC-Q1	60-0033011	varistor 2450V RV5/50	1	4,11 €
		60-1504	relay monostable 3w 24VDC 16A/400VAC	1	18,90 €
		60-154060	relay 24VDC 2xUM PLC-RSC-24DC/21-21	1	20,88 €
		60-154072	relay 230VAC 1x CO PLC-RSP-230UC/21AU	1	26,34 €
Fan	SC-E10, -E101	01-8319231	96R0x2 410% 2x150W compact resistor	1	97,23 €
		65-0507	SK Hygroskop Rittal SK 3118.000	1	106,65 €
Power unit	SC-G11	46-5070	stack fan	1	1.599,66 €
		46-5185	Radial fan with engine and-Inlet nozzle	2	260,10 €
Electrical Components	SC-T11	64-114820	Power Stack 3x1470 A SKM400GB126D TRENCH UL	1	21.103,32 €
		30-94074	power supply MINI-PS-100-240AC/24DC-C2LPS	1	193,47 €
		30-90380	buffer module C-TEC 2410-1	1	615,78 €
		30-90111	power supply MINI-PS-100-240AC/24DC/2	1	162,00 €
		04-035505	107µHx3 1300A aluminium threephase choke	1	6.820,29 €
		02-911002	100µFx3 750VAC/80A three-phase capacitor	2	193,68 €
		09-6075	temperature controller 03EN	2	4,80 €
		04-0215004	current transducer through-hole 1500A	3	211,95 €
		60-80012	current transducer through-hole 2000A	1	224,25 €
		09-02050	NTC 2K00 1% 60mW Epcos	3	2,10 €
Control Components	SC-A1	SC20CONT.GR-S1	Sunny Central controller board - SEMIKUBE	1	N/A
		SC20CAIO.GR1	IO-extension for SC20CONT	1	N/A
		41-5186	M12 cable 8pol 3m shielded	1	58,80 €
		43-9389	ISDN terminator 2x 100ohm in RJ45, BK	1	2,16 €
		42-5101	M12 terminating plug 8-pole	2	10,80 €
SC-W770, -W771, -W772, -W773, -W774	41-5190	voltage measuring cable between AC/DC	1	275,94 €	

# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

## O&M Contract Salient Point – **Spare parts**

TABLE 4 MINIMUM LIST OF SPARE PARTS (NON-EXHAUSTIVE)

No.	Spare part
1	Fuses for all equipment (e.g., inverters, combiner boxes etc) and fuse kits
2	Modules
3	Inverter spares (e.g., power stacks, circuit breakers, contactor, switches, controller board etc)
4	Uninterruptible Power Supply (UPS)
5	Voltage terminations (MV)
6	Power plant controller spares
7	SCADA and data communication spares
8	Transformer and switchgear spares
9	Weather station sensors
10	Motors and gearboxes for trackers
11	Harnesses and cables
12	Screws and other supplies and tools
13	Specified module connectors (male and female should be from the same manufacturer)
14	Structures components
15	Security equipment (e.g., cameras)

# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

---

## Operating Expenditure

### Typical items/costs to be included in OPEX

O&M cost incl. Maintenance reserve	Equipment replacement	Asset Management
Liability Insurance Property Insurance	Night consumption OPEX	Inverter Warranty extension
Land Lease cost	Land tax	Social Investment

OPEX typical range in the market : 7-12 EUR/kWp per year  
depending on the extent of the scope of works


# PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)

Operating Expenditure

$$\text{OPEX} = \text{O\&M} + \text{Asset Management} + \text{Replacements} + \text{Land Lease} + \text{Insurance}$$

## Opex buildup in 2018 for a fixed-axis PV system

Euros/MW/year



*Source: BloombergNEF. Note: Equipment replacement cost includes one inverter replacement during the lifetime of the plant. Insurance is assumed to be 0.25% of capex.*

**BloombergNEF**

# PV plant Operation and Maintenance (O&M)

## O&M Reporting

### Key elements of monthly O&M Report

- Preventive Maintenance
- Corrective Maintenance
- Facility Production and Consumption
  - monthly irradiance and production
  - monthly energy consumption
  - monthly inverter production
- Performance Ratio and Availability
- Spare Parts Management
- Security
- HSE



**Contents**

Glossary of Terms .....	5
1. Executive Summary.....	6
FACILITY ENERGY PRODUCTION .....	6
FACILITY ENERGY CONSUMPTION .....	6
FACILITY PERFORMANCE RATIO AND AVAILABILITY .....	7
2. Preventive Maintenance.....	8
3. Corrective Maintenance .....	9
4. Facility Production and Consumption.....	11
Monthly Irradiance and Production.....	11
Monthly Energy Consumption .....	11
Monthly Inverter Production .....	12
5. Facility Performance Ratio and Availability .....	13
6. Spare Parts Report .....	15
Summary .....	15
DIESEL GENERATORS FUEL CONSUMPTION .....	15
7. Security Report .....	16
Summary .....	16
Main Events .....	16
8. HSE Report .....	17
Summary .....	17
SUMMARY OF OPERATOR'S IMPLEMENTED MITIGATIONS AND MANAGEMENT OF RISKS ASSOCIATED TO THE COVID-19 PANDEMIC.....	20
9. SEDO Report.....	23

[sample O&M Report megawatt PV.pdf](#)



# Agenda

---

## GAF-RE Training Workshop Part II

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

# Plant fencing and anti-intrusion best practices

---

## Overview of the essential purpose

### Purpose

- For PV plant: security against external party **intrusion**, vandalism incident, public safety from **electrical hazard** (liability issue)
- For substation: public safety from electrical hazard, flashover incident, equipment tripping, unexpected plant shutdown
- For warehouse/laydown: prevention from theft incident, monetary loss, delay of project
- Unfenced site → consequences to **insurance** premium !??



### Best Practice

- Suitable **height** and **material** of fencing (e.g., galvanized steel)
- Preferably anti-climb fence – slightly higher cost
- Fencing pole to be provided with adequate **foundation** for strength and reliability
- Substation fence exposed metallic structure to be provided with suitable **earthing** according to local regulation
- Suitable lock and danger **signage** to be provided
- **CCTV** cameras for critical areas e.g., office, gate entrance, warehouse/laydown, substation. Preferably with night vision and adequate Uninterruptible Power Supply (UPS).
- Perimeter fence could be provided with lighting as necessary.



# Plant fencing and anti-intrusion best practices

---



Substation fencing following local regulation



Substation fencing following local regulation



Substation fencing should be lockable

# Plant fencing and anti-intrusion best practices



Suitable height and material of perimeter fence



Fencing pole provided with concrete stump



Fencing and gate is provided for laydown area

# Plant fencing and anti-intrusion best practices

CCTV and street lighting at gate entrance and fencing location



# Agenda

---

## GAF-RE Training Workshop Part II

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

## Compliance of ESHS – housekeeping

---

Housekeeping refers to Environmental and Health and Safety aspects that:

- ❖ Reduce potential for accident and incidents
- ❖ Ensure long-term gains vs short-term.
- ❖ Reduce exposure to penalties and financial costs.

<b>Good Housekeeping</b>	<b>Poor Housekeeping</b>
Waste sorted and stored appropriately	Fly waste all over property and surrounds
Bunded hydro-carbons	Oil spills, wastage resulting in costs
Good storage = good stock keeping	Poor storage = excess purchases and wastage
Better moral	No care attitude

**Housekeeping important for local and International Regulations and Standards.**

## ESHS housekeeping

### Best practices for proper housekeeping

Proper housekeeping must be provided on the construction site not only after completion of construction works, but continuously during construction.

#### Actions

- Periodical removal of trash and debris shall be organized
- all types of waste shall be collected and disposed of off site
- solid waste shall be kept in a covered container, construction waste shall be collected at a separately allocated area
- construction and packaging materials must be collected and stored properly and not be spread on site
- construction waste shall be transported from the area (usually it is Contractor's responsibility) and disposed of at the community landfill (landfill, dumpsite) upon written consent of the community head.

#### Objective


**Best practices for proper housekeeping**





# Compliance of ESHS – housekeeping issues that are common

---

- Agreements with local communities regarding Infrastructure
  - Domestic Waste
  - Hazardous / Industrial Waste
  - Construction Waste
  - Waste water discharge
  - Potable Water
  - Land use and access
- Drainage – to prevent erosion over time =prevent loss 
- Types of Waste and management
  - Hazardous/Industrial – hydrocarbons of any nature, construction materials, - handling and disposal
  - Construction – excess soil, rocks – removal to approved location, prevent dumping ground
  - Domestic – disposal, vermin, fly-waste – removal to approved location
- Fires –not acceptable for waste handling nor heating
- Heating Equipment – health and safety







# ESHS housekeeping



Construction debris left uncleared



Construction debris left uncleared



Rubbish from water bottles and plastics

# Agenda

---

## GAF-RE Training Workshop Part II

---

- 9 Efficient ways of pre-commissioning PV module string testing
  - 10 Weather station for on-site irradiation measurement and plant performance monitoring
  - 11 Bankable solar resource and energy yield assessments
  - 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
  - 13 Plant fencing and anti-intrusion best practice
  - 14 ESHS housekeeping
  - 15 Waste Management on and off site
  - 16 PV module disposal and recycling
  - 17 Environmental Offset, Botanical Studies
-

## Waste Management on and off site

---

### Construction period – construction waste

- ❑ Written consent with nearby settlement or community administration on final disposal of construction waste, excavated soil and stones
- ❑ For projects, which are subject of Environmental Impact Assessment (EIA), the EIA usually contains information on remaining soil volume and preliminary place where it will be disposed. For all cases, written consent shall be obtained.
- ❑ Remaining soil and excavation materials can be stored in PV area, compacted and levelled. If the soil and stones are finally dumped at a private land, then a written consent of the landowner should be provided.
- ❑ Construction waste shall be transported from the area (usually it is responsibility of Contractor) and disposed at the community landfill (landfill, dumpsite, other) upon written consent of the community head.
- ❑ Separate place for construction waste temporary collection shall be allocated on construction site, preferably it shall be fenced with a tape.

# Waste Management on and off site

## Construction period – construction waste

Inverter boxes



Construction debris



Excavated soil



Waste boxes



Waste boxes



Excavated soil



# Waste Management on and off site

Construction period – solid domestic waste

For domestic waste plastic or metal big containers with lid shall be installed at the site

Acceptable bin



Closed lid better



Waste left uncleared



Acceptable bin with lid



Waste left uncleared



Bin not used





## Waste Management on and off site

---

### Construction period – hazardous waste

- ❑ Hazardous waste is classified in accordance with the Decree of the Minister of Environment N 430 dated 25.12.2006.
- ❑ Barrels with transformer oil or diesel should be stored on a waterproof surface and under the cover to avoid direct sunlight.
- ❑ Secondary containment with a volume of 110% of the volume of drums or oil container shall be provided. The oil barrels/containers shall be properly labelled. The fire extinguisher shall be placed not far from the storage location.



# Waste Management on and off site

## Operation period

### Solid domestic waste

Transportation agreements shall be signed with local service provider for periodical transportation of generated waste during operation, construction and domestic waste from the area to designated landfill

### Hazardous waste

#### Transformer oil or diesel containers

- ✓ Barrels with transformer oil or diesel should be stored on a waterproof surface and under the cover to avoid direct sunlight.
- ✓ Secondary containment with a volume of 110% of the volume of drums or oil container shall be provided.
- ✓ The oil barrels/containers shall be properly labelled. The fire extinguisher shall be placed not far from the storage location.



# Agenda


---

## GAF-RE Training Workshop Part II


---

- 9 Efficient ways of pre-commissioning PV module string testing
- 10 Weather station for on-site irradiation measurement and plant performance monitoring
- 11 Bankable solar resource and energy yield assessments
- 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
- 13 Plant fencing and anti-intrusion best practice
- 14 ESHS housekeeping
- 15 Waste Management on and off site
- 16 PV module disposal and recycling
- 17 Environmental Offset, Botanical Studies


# PV module disposal and recycling




Studies have shown the heavy metals in solar panels — namely **lead** and **cadmium** — can leach out of the cells and get into groundwater, as well as affect plants. These metals also have a record for detrimental effects on human health. Lead is commonly known to impair brain development in children, and cadmium is a carcinogen.



Recycling of crystalline silicon and CdTe photovoltaic module



# Commercial Module Recycling Processes



# PV module disposal and recycling

Sample of damaged PV modules

Broken glass



Broken glass




Delamination



Temporary storage of broken panels, wrapped



S323Doc



Kept of floor



# Agenda

---

## **GAF-RE Training Workshop Part II**

---

- 9 Efficient ways of pre-commissioning PV module string testing
- 10 Weather station for on-site irradiation measurement and plant performance monitoring
- 11 Bankable solar resource and energy yield assessments
- 12 PV plant Operation and Maintenance (O&M), operation expenditures (OPEX)
- 13 Plant fencing and anti-intrusion best practice
- 14 ESHS housekeeping
- 15 Waste Management on and off site
- 16 PV module disposal and recycling
- 17 Environmental Offset, Botanical Studies



## Environmental Offset, Botanical Studies

---


Biodiversity offsets are **measurable** conservation outcomes that result from actions designed to compensate for **significant, residual biodiversity loss** from development projects.

Biodiversity offsets are based on the premise that impacts from development can be compensated for if sufficient habitat can be protected, **enhanced** or established elsewhere.

Biodiversity offsets are **economic instruments** and are based on the polluter pays approach, and are measurable.

# Environmental Offset, Botanical Studies


Figure 2. **The mitigation hierarchy**



Source: Adapted from Rio Tinto (2012). *Rio Tinto and Biodiversity: Working Towards Net Positive Impact*, Rio Tinto PLC, London, UK, Rio Tinto Limited, Melbourne, Australia. Available at: [www.riotinto.com/ourcommitment/features-2932\\_8529.aspx](http://www.riotinto.com/ourcommitment/features-2932_8529.aspx).

# Environmental Offset, Botanical Studies


---





OFFSET NOT FINANCIAL PENALTY BUT MEANS TO ENSURE SUCCESS OF SPECIES.

# SPECIALLY PROTECTED NATURE AREAS OF ARMENIA

- **State Reserves**
- <<Khosrov Forest>>
- <<Shikahogh>>
- <<Erebuni>>
  
- **National parks**
- <<Dilijan>>
- <<Lake Sevan>>
- <<Lake Arpi>>
- <<Arevik
- **26 State Reservations**
- **230 Nature Monuments**





## Data: Key Biodiversity Area Protection

Country: Armenia

### Data Sources:

World Database of Key Biodiversity Areas. Developed by the KBA Partnership (BirdLife International, International Union for the Conservation of Nature, Amphibian Survival Alliance, Conservation International, Critical Ecosystem Partnership Fund, Global Environment Facility, Global Wildlife Conservation, NatureServe, Rainforest Trust, Royal Society for the Conservation of Birds, Wildlife Conservation Society and World Wildlife Fund); UNEP-WCMC, IUCN, and NGS, 2018. Protected Planet: The World Database on Protected Areas (WDPA) [On-line], October 2018. Cambridge, UK; UNEP-WCMC and IUCN; Flanders Marine Institute (2018). Maritime Boundaries Geodatabase: Maritime Boundaries and Exclusive Economic Zones (200NM), version 10; Global Administrative Unit Layers (GAUL), 2015. UN Cartographic Unit





## Contact

Fichtner GmbH & Co. KG  
Sarweystrasse 3  
70191 Stuttgart  
Germany

[www.fichtner.de](http://www.fichtner.de)



### Sven-Malte Störring

Phone +49 (711) 8995-201  
Mobil +49 (163) 8995 201  
[sven-malte.stoerring@fichtner.de](mailto:sven-malte.stoerring@fichtner.de)



### Christina Mansfeld

Mobil +27 (72) 449 0353  
[mansfeldc@fis.fichtnergrou.com](mailto:mansfeldc@fis.fichtnergrou.com)